



An Electricians Guide

We all know Electricians are absolute legends, but even legends need some guidance from time to time.

This guide was written by electricians for electricians. It is designed to help you unlock the power of the CATCH Control **6 Channel**.

CATCH Power A trademark of Project H Pty Ltd 180 Dumaresq Street Glen Innes NSW 2370 Australia Ph: +64 2 5700 5717 W: www.catchpower.com.au E: sales@catchpower.com.au

<u>1 - Getting the right software on your phone.</u>

You will need **BOTH** of these.. Download them from your phone's app store.



CATCH Power Configurator



The Monocle

CATCH Power

The "CATCH Power Configurator" is used for setting up the hardware while you are on site.

"The Monocle" is the CATCH Power monitoring platform used by you and your customer for consumption monitoring and load control

"My Fleet Manager" is where you can log in to view your fleet of installations from the office. This platform is available on the computer and provides historic site data while allowing you to monitor and make changes to your sites remotely. Log in with your installer log in at <u>https://myfleet.edde.world</u>



ARE YOU UP FOR THE CHALLENGE?

Throughout this manual we assume you are a **CUTTER** quality electrician. If you are scratching your heading wondering how to download an app onto your phone you may want to give this job to somebody else...it only gets more technical from here.

2 – Create your Configurator Account



CATCH Power Configurator CATCH Power

Use the CATCH Power Configurator App on your phone for this...open it.

1. Click on the menu button on the top left.

■ Live Data	(C) 🎉	
¢.	A device is not currently connected.	
	Connect to Device	< Main Menu
		Device Management
		Live Data
		Device Settings
		Firmware Updater
		Get Firmware
	_	Sites Management
		2. Click Here
	Ļ	Account Management
		Your Account
		Logout

<u>2 – Create your Configurator Account...Cont'd</u>

3. If you already have a Configurator account put the username and password in here.

		(0) 🔏
	Login	
	Email	
	Password	8
	Log in	
4. Need to create a new Account?		
	Other Actions	
	Enter Access Code	>
	Request Access Code	>
	Create Account	>



SUGGESTION!!

If you have multiple contractors doing work for you then we suggest you create a single company wide account and have everybody log in using that account..

we aren't NETFLIX, we are happy for you to share.

2 – Create your Configurator Account...Cont'd

5. You know what to do here Usernam password please.	ne and
	X Create Account
	Email
	Password
	Role
	Installer
	Create

AND YOU ARE DONE... OFF TO SITE WE GO.



IMPORTANT!!

Check your email address before pressing save...an incorrect email address is going to mean you miss out on heaps of cool features...



AUTO LOGIN

The configurator will keep you logged in for a few days, but for security reasons it will ask you to re-login every now and then, so you need to store the username and password away somewhere. You might be cutter Spec, but you're not superman/woman, you will forget the login details for sure.

Hardware Installation Overview

Before getting started with the details. Lets go over some of the features of the 6 Channels Device:

- Works with Single Phase, 3 Phase, or split phase.
- Has 6 measurement channels that can all be configured to measure different things.
- There is a 240V AC Output designed to drive a contactor.
- There is a dry contact output designed to control a small relay coil or be connected to a set of DRM terminals.

The installation process is broken down into 4 steps:

1. Getting power to the unit.

This is different depending on whether you are installing single, split, or 3 phase...so pay attention to this.

2. CT Placement.

There are 6 of these that can be used. Its easy to make mistakes here, so make sure you follow the process outlined in this section.

3. Load Control.

Connecting the loads to the relay.

4. Inverter Control.

Connecting any solar inverters you may have to the relay.

Hardware Installation Overview

There are a few things to Note:

When talking about multi phase electrical installations electricians are used to using Red/White/Blue or Phase 1/2/3 for referencing the different phases.

WE DO NOT USE THAT TERMINOLOGY.

All through this document you will see references to Phase R/S/T, and that is how we refer to the different phases. It is the same thing as what you would typically be used to but it's just a little more relevant in an international setting.

Phase Rotation:

Phase rotation is not important when installing CATCH Control. It does not matter which phase is plugged into the R/S/T terminals. Phase rotation can be clockwise or anticlockwise...we don't care.

Phase Matching:

THIS IS VERY IMPORTANT ..

Phase matching refers to ensuring the CTs that are measuring current are on the correct phases. We will have much more to say about this later. But for now, know your biggest headache is likely to be Phase Matching your CT's

Hardware Installation Physical Connections



Hardware Installation Logical Connections

The previous page showed you where the connection ports are physically located for terminating on the CATCH Control 6CH device. However, that image makes it too hard to explain what is happening.

We will use the below LOGIC connection diagram for the rest of this document to describe how to wire the unit and what it is cable of.

As a Cutter Spec electrician I'm sure you can join the dots.



Voltage Input:

The voltage input terminals are where CATCH Control measures voltage used to calculate power.

Voltage Input pin (**R**) is also used to as a source of power for the CATCH Control and also to send power to the OUT(R) pin when needed.



These pins get connected differently depending on whether you are single phase / split phase / 3 Phase



OUT (R):

This is a 240V AC Output that can be used to drive a contact coil.

It is connected to voltage ref (R) via a solid-state switch.

IT IS NOT DESIGNED TO CARRY LARGE LOADS.



A typical connection to a contact is shown below. This is a typical 3 phase site. Note that the Neutral connector is shared.





IMPORTANT!!

OUT (R) is connected to the contactor A1/A2 COIL terminals..not the Load terminals...you will create smoke if OUT (R) is connected to the load.

CT channels:

The CTs on the 6 channel device can be mapped to do what ever you need, however there are some things to note so you don't fall into CT hell.



By default, the CT channels are phase matched to the below phase voltage channels. This can be changed in the configurator app if needed, buts it is best to keep them as defaults if you can.



CTs...CONTINUED:

- Only use compatible CT's supplied by CATCH Power.
- The CT's should ALWAYS be placed on the active Wire, never the Neutral.
- Always terminate the CT into the Device BEFORE clamping it around the wire.
- Label your CTs as you go..6 CT's are difficult to sort through after installation.
- As you install each CT perform a PULL test on each wire to make sure there is a good electrical connection.
- The stripped end of the CT wires is the PERFECT length for the connector...don't cut them, solder them or fold them.. (even if you think it would be better if....) don't do it. All you need to do is push down on the terminal latch and push the wire in. There should be no exposed conductor, push it all the way in.
- If you don't need all the CT's you don't have to install them into the Unit.

Hardware Installation Power & CT's

- Only use compatible CT's supplied by CATCH Power.
- The CT's should ALWAYS be placed on the active Wire, never the Neutral.
- Always terminate the CT into the Device BEFORE clamping it around the wire.



From left to right the wires go white/black as shown.

Every CT wire has its own terminal.



Hardware Installation RS485

The 6 Channel CATCH Control acts as An RS485 slave device.

The RS485 interface can be used to query measurement data and control load outputs, but the interface is typically used to allow the CATCH Control to act as the energy meter for a wide range of Solar Inverters.



For details on specific RS485 inverter connections visit the Catch tech docs page. www.catchpower.com.au/tech-docs



Hardware Installation TS485

The RS485 interface is MODBUS over RS485. Good RS485 installation techniques are required to ensure a reliable connection.

The highlights are below:

- Use CAT6 or equivalent cable. The voltage rating needs to be 600V or better as it is being run through the switchboard.
- Use a twisted pair as the A and B conductors (ie Blue and Blue Strip).
- Keep the cable away from large current carrying conductors if possible.
- For runs longer than 10m terminate the Solar Relay end with the 120 Ohm resistor supplied in the box.

When terminating with the resistor follow the technique below.



2. Bend one side of the resistor lead over as shown for a clean termination



Hardware Installation LOAD CONTROL - DRM

DRM:

The DRM terminals are a solid state relay (SSR) giving a dry contact used for control of a load.

The CATCH Control 6CH DRM switch can be used to switch small loads directly or to drive a DC coil relay for control of larger loads.

Part 1 provides the specifications for the DRM solid state switch. Part 2 provides some applications and examples of using the DRM switch to control loads.



Part 1: DRM solid state switch specifications.

The DRM switch is AC or DC tolerant (non-polarized terminals). It is an isolated (floating) switch.

The solid state switch will fail if the following absolute maximum ratings are exceeded.

Absolute maximum ratings:

- Voltage rating: 48 V peak (33.9 V AC rms or 48V DC).
- Current rating: 400 mA peak (282 mA AC rms or 400 mA DC).

- Isolation voltage rating (between SSR input & output contacts: 5000 V. Electrical Characteristics:

- On state resistance: 2.5Ω (maximum).



IMPORTANT!!

Switching inductive loads (including relay coils) without a freewheeling diode will result in voltages in excess of the absolute maximum rating (SMOKE!).

Hardware Installation LOAD CONTROL - DRM

Part 2: DRM load control implementation

The DRM solid state switch can be used to control/switch loads in one of two ways.

Implementation 1: Direct control of a small loads

The DRM can switch a small AC or DC load with ratings less than the absolute maximum specifications provided in part 1. Examples include:

- 24V DC or AC LED.
- 24V DC alarm.

- Signalling a Demand Response Mode (DRM) to a device with a DRM interface (such as an air-conditioner).

IMPORTANT!!

- Small inductive **AC** loads **cannot** be controlled directly.
- Small inductive **DC** loads may be controlled directly if a freewheeling diode is implemented across the inductive load (see implementation 2).

Application 1 example – Control of an AC or DC Alarm using DRM output



Application 2 example – Controlling an air-conditioner using the DRM output connected to the DRM interface of the air-conditioner



Hardware Installation LOAD CONTROL - DRM

Part 2: DRM load control implementation... CONTINUED

Implementation 2: Indirect control of a large loads using DRM output and a DC relay

The DRM can switch larger loads indirectly using a DC relay. The relay **must** have a coil which can be excited with a DC source and **must** also be excited with a DC source. A freewheeling diode **must** be implemented across the inductive DC coil.

Application 3 example – Indirect control of large load using the DRM output and a relay with a DC coil (note it may be difficult to source a DC relay which can switch large loads and therefore an additional contactor may be required (as shown below)).



Typical Installation 3 Phase



NEUTRAL

Even legends make mistakes.. Don't leave site without testing the installation



CATCH Power Configurator CATCH Power

Test 1 – Apply power to the CATCH Solar Relay

Did smoke come out? If no, congratulations you have passed test 1.

But in all seriousness. When power is applied to the Solar Relay the Power and Bluetooth light will flash on and off for about 20sec, then just the power light will stay on.

The rest of the tests will be done from within the CATCH Configurator App.

Open the Configurator and connect to your device. As shown below

C CATCH Power Configurator	Press the connect button. The serial number will appear in the list	← CAICH Peare Configuration X Scan Page ✓ 42424-SR6e/CATCH 7C877CE:59:F5:82 RSSI: -30



Things change quickly.. And CATCH Power is no different. By upgrading your firmware, you ensure your device has all the bells and whistles.





READ THE TIPS FOR UPDATING

There is a little story on the firmware update screen... read it. It will help make your firmware upgrade process seamless.

CT Configuration

SETUP

← CATCH Power Configurator ··· – Main Menu	Navigate to the De the process of con	vice Setting fiaurina the	js page to start CT's.
Device Management	_	<u>j</u> j j	
Live Data			
Device Settings			
Firmware Updater	All 6 CTs need to be co	nfigured. Click	on the down arrow to
Get Firmware	open up the configurati	ion for that part	ticular CT.
Sites Management			
Sites			
Account Management			
Your Account			
Logout			
	Channel 1	^	
	Mains	\$	
	Reverse CT		
	No	0	
Channel 2			
Observal 2	3003		
Channel 3	Phase		
	Phase R	\$	
Channel 4			
Channel 5	~		
Channel 6	~		

PURPOSE:

Every CT needs to be allocated a **Purpose**. We have 3 purposes that can be used.

MAINS:

A Mains CT is one that is monitoring the export and import on the property.

SOLAR:

A Solar CT is one that is monitor some form of solar.

OTHER:

These CT's measuring generic loads such as hot water services, heating circuits, etc.

Reverse CT:

This is the same as switching the physical CT around in the switchboard. You wont need to change this. You and the CATCH support team can change this setting remotely which is very handy if you notice the CT was around the wrong way after you have left site.

CT Ratio:

If you are using a non standard CT the CT ratio can be adjusted, however don't do that. Use the standard CATCH CT's and leave this as 3003.

Phase:

The voltage phase this CT is mapped to. If you are on a split phase site you will need to remap CT 3 & 4 away from Phase S because phase S cannot be connected in a split phase configuration.



Default CT Channel Mapping

CT Configuration

СНЕСК



Navigate to the **Live Data** page to start the process of checking your CT's.

Remember your CT channel numbers are as shown below.



Readings - Cha	annel 1	
Power:	3.00	kW
Amps:	13.00	А
Power Factor:	0.98	
VA:	3.00	kVA
VAR:	0.20	kvar
Exported:	0	Wh
Imported:	0	Wh
Purpose:	Measure Mains	
CT Reversed:	No	

An Example of a MAINS configured CT Channel. This is Channel 1.



Navigate to the **Live Data** page to start the process of checking your CT's.

Remember your CT channel numbers are as shown below.



Readings - Cha	annel 1	
Power:	3.00	kW
Amps:	13.00	А
Power Factor:	0.98	
VA:	3.00	kVA
VAR:	0.20	kvar
Exported:	0	Wh
Imported:	0	Wh
Purpose:	Measure Mains	
CT Reversed:	No	

An Example of a MAINS configured CT Channel. This is Channel 1.

Understanding if your CT's are installed correctly can take a bit of practice. Some helpful tips are outlined below

Bad Connection:

If there is a bad connection on one or both CT wires you will get either ZERO or VERY HIGH readings for Amps.

2	Zero reading		V	ery HIGH	
Amps:	0.00	А	Amps:	480	A

Current reading but no power:

This typically means the CT needs to be remapped to a phase that has a voltage on it. You will get this type of problem in split or single-phase environments where not all voltage inputs are being used.

Power:	0.03	kW
Amps:	12.0	А

Lower power factor:

This typically means the CT is on the wrong phase and needs to be moved. This is only true if you have power above 500W. When there is little to no power, power factor will be low (almost zero), and this is normal. But if you have power above 500W and low power factor this is an indicator you have the CT on the wrong phase. You can either remap it in the configurator setup or physically move the CT.

Power:	1.54	kW
Amps:	12.0	A
Power Factor:	0.56	
VA:	3.00	kVA
VAR:	1.32	kvar

Incorrect Direction:

If the CT arrow is not pointing in the right direction your power numbers will be in the wrong direction.

With CATCH Control we show exporting power as a negative number and importing power as a positive number.

Pay special attention to the sign of the power numbers of each CT. The best way to check is to follow the procedure below:

1. Shut down all Solar and Battery systems.

All MAINS ct's should show a POSITIVE power number.

All SOLAR ct's should read ZERO.

2. Start Up the Solar (LEAVE BATTERIES OFF)

After the inverters have started up

All SOLAR ct's should read a NEGATIVE power number.

Load Control

SETUP

Output Configuration	\sim		
Override 1		Output Configuration	/
Override 2	~	AC Output On When threshold Reached	\$
Override 3	~ \	DRM Output On When threshold Reached	\$
Override 4	~		

Decide how you want your outputs to operate.

On when threshold Reached:

is equivalent to a normally open switch.

The Contact is not energized until a certain criteria is met, then it is energized.

The DRM output is open circuit until the criteria is met then it becomes a closed switch.

Off when threshold Reached:

is equivalent to a normally closed switch.

The Contact is energized until a certain criteria is met, then it is deenergized.

The DRM output is a closed circuit until the criteria is met then it becomes an open switch.



Schedules Setup:



Yes: The schedule is active. No: Schedule is not active. All currently active scheduled will have a solid circle in their title.

Туре

Export Control

 \diamond

The type of control scheme to apply. Valid options are:

Export Control:

When using Export control a channel is monitored for power and when power goes above and below a particular threshold the output is triggered.

Turn On: The output is turned on.

Turn Off: The output is turned off.

Top Up:

This is a special mode that provides a guaranteed run duration for a day. This mode is used as a safe guard when controlling hot water to ensure there is enough heating of the hot water even on cloudy days. (see hot water scheduling example below for a example of Top Up implementation).

Voltage Controlled:

The output is turned on and off based on voltage thresholds.

Frequency Controlled:

The output is turned on and off based on grid frequency thresholds.

Current Controlled:

The outputs are turned on or off based on the current flowing through a ct channel.

Schedules Setup..continued:

Output

AC

 \diamond

Which output should this override be controlling.

Channel

MAINS 🗘

When Export control or Current Control are chosen as a control scheme they need to CT channel to use as a measurement reference. This is where you set the channel. You can choose on one of the 6 CT channels, plus two special channels.

Channel 1-6:

The override will used this channel for the threshold measurements.

MAINS:

All CT's with the purpose of MAINS will be summed together and used as the measurement reference.

SOLAR:

All CT's with the purpose of SOLAR will be summed together and used as the measurement reference.

Only When

ignore

 \diamond

A value of ignore means this override will run when the time and thresholds dictate. This is a stand-alone override.

If you choose an override, all the conditions of this override must be met, plus the chosen other threshold must be running.

Note you need to make sure you don't link to another override that is controlling the same output, this will result in this override never running.

Schedules Setup..continued:

Start Time

	5			
	6		am	
	7	00	pm	
	8	01		
	9	02		
Stop Ti	me			
	12			
	1			
	I		am	
	2	00	pm	
	3	01		
	4	02		

The time period that this override should be considered.

If the end time is greater than the start time it is assumed the period for this override is with in the same day.

If the end time is less than the start time it is assume the override starts today at the designated start time and ends tomorrow at the specified end time.

When overrides for the same output overlap in time period the override with its start time closest to the current time is considered the active override.
COMMISSIONING Load Control

Schedules Setup..continued:

Minimum On Time (mins)

0

When the conditions of this override result in the output being activated, this defines how long the output has to stay active before it can be turned off.

Minimum Off Time (mins)

0

When the conditions of this override result in the output being turned off, this defines how long the output has to stay off before it can be activated again.

Above Threshold

3600

Above Time (mins)

0

When the measurement value has been above this number for the number of (<u>above</u> <u>time</u>) minutes the specified output should activate. In the above example the number is power (3600W), so the override type would have been Export Control

Below Threshold

0

Below Time (mins)

0

When the measurement value has been below this number for the number of (<u>Below</u> <u>time</u>) minutes the specified output should turn off.

COMMISSIONING Load Control

Some Scheduling Examples:

Hot Water Control:

The home owner is a large user of hot water, however they have a very large solar system. It has been decided there needs to be at least 4hrs of heating, and if it couldn't be done with the solar they want it done at 10pm because electricity is very cheap then.

	Start Time: 7am Stop Tim	ie: 2pm		
ide 1	Type: Export Control	output: AC	Channel: MAINS	Only When: Ignore
Overr	Minimum On Time: 5min		Minimum Off Time:	0min
	Above Threshold : 3600 Below Threshold : 0		Above Time : 5 min Below Time : 0 min	
	Start Time: 10pm Stop Ti	me: 2am		
ride 2	Туре: Тор Up	output: AC	Channel:	Only When: Ignore
Overi	Minimum On Time: 0min		Minimum Off Time:	0min
	Above Threshold : 0 Below Threshold : 0		Above Time : 0 min Below Time : 0 min	

Override 1 is set so that when the hotwater element size is being exported to the grid by the solar system for 5min the hot water turns on. We have specified the 5min because we don't want the HW to come on until the solar is really ready to handle it. The min run time is there is that the hot water does not rapidly switch on and off, the 5 minutes gives the solar plenty of time to ramp up and handle the load.

Override 2 is Topup and is set for 4hrs starting at 10pm. Note the Topup time period defines the total duration we want the hot water to have heated. If 50% of the 4hrs was already managed during the day then the topup mode will start at 10pm and only run for 2hrs.

COMMISSIONING Load Control

Some Scheduling Examples:

Hot Water Control + Air Conditioner Control:

The hot water requirements are the same as the previous example, except this time the home owner wants the air conditioner to run on surplus solar ALL DAY.

	Start Time: 7am Stop Time	e: 2pm		
ide 1	Type: Export Control	output: AC	Channel: MAINS	Only When: Ignore
Overr	Minimum On Time: 5min		Minimum Off Time	e: Omin
	Above Threshold : 3600 Below Threshold : 0		Above Time : 5 mir Below Time : 0 mi	า ท
	Start Time: 10pm Stop Tin	ne: 2am		
ride 2	Туре: Тор Up	output: AC	Channel:	Only When: Ignore
)veri	Minimum On Time: 0min		Minimum Off Time	e: Omin
U	Above Threshold : 0 Below Threshold : 0		Above Time : 0 miı Below Time : 0 mi	n n
	Start Time: 7am Stop Tim	e: 2pm		
ride 3	Type: Export Control our	tput: DRM (Channel: MAINS	Only When: Override 1
Jveri	Minimum On Time: 0 min		Minimum Off Time	e: 5 min
-0-	Above Threshold : 1500 Below Threshold : 0		Above Time : 5 mi Below Time : 0 mi	n n

Override 3 has been tied to the Hot water override. It is harder to find the energy to turn on the large 3.6kW hot water load than it is to find 1.5kW for the Air conditioner so we only allow it to run after the hot water has turned on.

COMMISSIONING

Energy Meter

SETUP

COMMISSIONING Energy Meter

← CATCH Power Configurator	–
< Main Menu	
Device Management	
Live Data	
Device Settings	
Firmware Updater	
Get Firmware	
Sites Management	

Navigate to the **Device Settings** page to start the process of configuring the Energy Meter

The CATCH power tech docs page has more details on how to setup for specific inverters, but the process is pretty much identical across all inverters that we act as the energy meter for.

- Connect the RS485 interface as per the inverter requirements.
- Choose the energy meter in the Emulated Meter drop down box.

All of the modbus RTU parameters will default for the specified inverter so there is no need to change anything.

hodbus Configuration	^
Emulated Meter	
CATCH Power	\diamond
Modbus Device ID	
1	
Modbus Baud Rate	
57600	
Modbus Stopbits	
1	\diamond
Modbus Parity	
None	\diamond
Long Power	
false	\diamond

COMMISSIONING

Energy Meter

СНЕСК

Testing the Installation Energy Meter

Step 1 – make sure your inverter is on and configured for an energy meter.

You will know if the RS485 is or is not working because the inverter will have a fault code on it.

If your inverter is not detecting the energy meter the steps below can help you trouble shoot.

Step 1 – Navigate to the Live data screen on the Configurator.



WELL DONE... If the RS485 looks like the screen above all is good.

COMMISSIONING

WiFi Connect

SETUP

COMMISSIONING WiFi Connect

← CATCH Power Configurator	–
< Main Menu	
Device Management	
Live Data	_
Device Settings	
Firmware Updater	
Get Firmware	
Sites Management	

Navigate to the **Device Settings** page to start the process of configuring the WiFi settings

All CATCH Control devices should be connected to the internet, it is not a mandatory requirement, but is strongly recommended.

CATCH Control uses the owners WiFi system to connect to the internet. Click on WiFi settings and enter the access point name and password.

	WiFi Settings
	Access Point
Wifi Settings Connection: No WiFi Change WiFi Settings >	Glen Solar Security Type WPA/WPA2 Personal Password Wifi password
The WiFi Scan button will show you a lis and their signal strengths.	st of networks Part of networks The static stat

COMMISSIONING WiFi Connect

<u>A Quick discussion on WiFi Signal Strength</u>



-30dB to -60dB : Good Strong signal
-60dB to -70dB : Average Signal
-70dB to -80dB : Weak and potentially troublesome signal
-90dB : All most no signal
Small changes in the signal strength matter:
Every -3dB is a halving of the signal strength.
As an example. -60dB is twice as strong as -63dB. And 10x stronger than -70dB.



To ensure trouble free operation of the CATCH Control, ensure the Wi-Fi signal just outside the switchboard is at least

-64dB or better.

How can you check the signal quality?

The best option is to use a Wi-Fi signal checker. There are many of them available for your phone. One that we use regularly is show below. It will give you the signal strength in dB.



WiFi Analyzer olgor.com Tools E Everyone Contains ads O This app is available for all of your devices

COMMISSIONING

WiFi Connect

СНЕСК

COMMISSIONING WiFi Connect



Navigate to the **Live Data** page to start the process of checking WiFi status

Scroll to the bottom of the page and check the WiFi State.

WiFi State	
Server Status:	Server Good
My IP	192,168,1,219

There are a number of different statuses that can appear here:

Server Good:

The Solar Relay has connected to the internet.

IP Assigned:

The Solar Relay has connected to the local network, but cannot connect to the Internet. This could mean a weak WiFi signal, or port 443 on the customers router is blocked.

WiFi:

Connection to the WiFi router was successful, but the DHCP server did not allocate an IP address. You may need to configure a static IP.

No WiFi:

Cannot connect to the WiFi router. The SSID and password could be wrong, or a weak signal.

Testing the Installation



WELL DONE...

All of your hardware is installed correctly

Summary of Steps

- 1. Create a new Site
- 2. Attach the Solar Relay to the site
- 3. Activate the Solar Relay WiFi so that it can send and receive messages.





CATCH Power Configurator CATCH Power

Use the CATCH Power Configurator App on your phone for this... open it.





Creating the Site



Attach the Solar Relay to the Site

1. Press the action button and choose Add Device	Address 180 DUMARE GLEN INNES,	SQ STREET NSW 2370	
	Devices		
	CATCH Re Model No. 1 Serial No. 9	elay WiFi 10003 001	
	CATCH R Model No. 1 Serial No. 9	elay WiFi 10003 002	
	CATCH Re Model No. 1 Serial No. 9 CATCH Re	elay WiFi 0003 003 elay WiFi	
	Model No. 9 Serial No. 9	Add Device	
		Edit Site	>
	Users	Add Installer	
	Owners		

This particular site already has 4 Solar relays attached to it.. but we are adding one more.

Attach the Solar Relay to the Site



Press "Submit Device" And you are done.. the Monocle has been configured.

At this point you have create the site and attached the device, and all of this information has been sent to the MONOCLE.

As part of the site creation process, an email has been created and sent to the customer (remember the site Owner email address). The instructions for how the customer can get access to the MONOCLE are in that email.

The email to the customer will contain an **access token** the customer will need in order to register themselves as the owner of the site you have just created.

The last thing for you to do is connect the Solar Relay to the customers WiFi and check everything looks ok in the MONOCLE.

Dynamic / Flexible Exports

The following requisites are required before beginning this step:

- The Solar Relay is connected to the local WiFi
- The Solar Relay is registered with the MONOCLE.

(See Previous Steps for details)



Dynamic / Flexible Exports



Dynamic / Flexible Exports

The screen Auto refreshes. The last refresh time is here

It may take a few minutes, but you need all crosses to turn GREEN.

The default and active export limits for the site are shown here:

Last Updated: 8/6/23 12:37.47 PM **Status** Scroll down The indicators below are update 30sec. You need to get green ticks items below in order for Dynamic exp to be operational. Inverter Control Scheme: MIXED Registered with CATCH CSIP-X AUS This indicates all the criteria have been met for us to register this site. as a Dynamic Export site. We require Dynamic Exports to be enable and a valid NMI to be supplied. Registered with SA Power Х Networks LFDI: N/A This indicates the NMI has been accepted by the DNSP system. The LFDI is the unique identifier used by CATCH and the DNSP to identify this site. You can copy the LFDI by pressing the copy icon to the right. Measurement Data has been х sent. Last Measurement sent: 1/1/70 10:00 AM Measurement data has been successfully sent from this site to the DNSP. **Received Active Controls** X Default Export(W): N/A Active Export(W): N/A Last Control Received: 1/1/70 10:00 AM Indicates we have successfully received some active export controls from the DNSP. Errors no errors

AND WE ARE DONE...

111

 \bigcirc

<

"My Fleet Manager"

Remote Control of your Fleet

Access your fleet of installations at https://myfleet.edde.world

1. Log in using the same installer "log in" you use for The Configurator App.

2. Make changes to your sites from the computer. Access a site remotely and change the configuration, monitor the historic consumption data, view the version of the firmware, check the WiFi signal strength and more.

Device D	etails
Configu	Iration
۲	System Override 1
۲	System Override 2
0	System Override 3
0	System Override 4
Gene	al Configuration
Frequ	ency Control
Volta	je Control
Expo	t Control
Modb	us Configuration

DIAGNOSTICS, REMOTE CHANGES & MONITORING

"My Fleet Manager" Remote Control of your Fleet

Device Details

Identity	
Serial#	
FW Ver	3072
Туре	CATCH Relay E-series
Device time	3:16 pm
Details	phase 1

Override Control

ON	OFF
RELEASE	
Runtime:	108 mins
Please Note: Turni overriding the dev in place until the r	ing a device on or off here is rices own logic. This will remain elease button is activated.

Watt Hour Data		
Ch1 Exported	-10341 Wh	
Ch1 Imported	46 Wh	
Ch2 Exported	-13147 Wh	
Ch2 Imported	0 Wh	

DIAGNOSTICS, REMOTE CHANGES & MONITORING

"My Fleet Manager"

Remote Control of your Fleet

Connection Status (ONLINE)

ONLINE
1
1
3958

Wifi Information





DIAGNOSTICS, REMOTE CHANGES & MONITORING

The last step is to check the MONOCLE and make sure everything looks ok from the customers point of view.





24hr ENERGY SUMMARY

If this is your very first Monocle site, the site should open as the default site, and the data should be displayed as shown here.

If you have more than one site you may need to go and find it.

Change Sites on the Monocle.









24hr EN	ERGY SUM	IMARY	
	0	<	



Ш

0

<

Dynamic / Flexible Exports

If the site is participating in a DNSP dynamic / Flexible Exports program then Derick the Dynamic Gateway control should be present, letting you know the current site export limit. The current site Export limit is 15kW

The technical term for an EV Charger is **E**lectric **V**ehicle **S**upply **E**quipment (or EVSE for short).

You can't just get any old EVSE. The EVSE needs to be OCPP compliant and support the *Smart Charging* profile.

You can go to our website for a list of EV Chargers that we have tested and know will give you trouble free charging. <u>http://www.catchpower.com.au/evse</u>

<u>1 – Adding the EV Charger to the CATCH Site</u>

• Open the "CATCH Power Configurator", Log in with your installer account.



Open the menu and click on the **Sites** menu Option

> Click on the Site you wish to register he EV Charger against.

Note: This is a new Site you will need to create it by pressing the orange button in the bottom right.

<u>1 – Adding the EV Charger... continued</u>

- 0	CATCH Power Configurator ··· - C X	
=	Beta Site Overview 💿 🌋	
A	Address	
1	80 DUMARESO STREET	
G	GLEN INNES, NSW 2370	
D	Devices	
	CATCH Control E-series	
	Model No. 10004 > Serial No. 2898	
	CATCH Control E-series	
	Model No. 10004 > Serial No. 3993	
	CATCH Control E-series	
	Serial No. 3602	/
	CATCH Control E-series Add Device	
	Model No. 10004 Serial No. 3633	/ /
	CATCH Control E-series Add Installer	
	Serial No. 6262	
	CATCH Control E-serie	/
	Serial No. 8075 Dynamic Export	
	CATCH Control E-series	
	Model No. 10004 Serial No. 5167	

Click on the orange circle in the bottom right. Then click on **Add EV Charger**

<u>1 – Adding the EV Charger... continued</u>

Fronius WattPilot 💠	•	
ettings		
Name *		
Phases *		
1 🗘 🔸		÷
Connectors *		
Current Limit (A) *		
32	•	 -

Choose the inverter Brand. If your brand is not there Choose Generic OCPP.

Give it a name

Is it single or 3 phase

This will limit the per phase charging current to this value.



1 – Adding the EV Charger... continued

Device Details	
Name: WattPilot	
ID: 0000-0001-00	
Settings	
Name *	
WattPilot	
Phases *	
1	\$
Connectors *	
1	
1 Current L	
1 Current L [*] (A) *	
1 Current I: (A) * Scroll down	
1 Current Lo (A) * Scroll down	
1 Current 1: (A) * Scroll down Setup Information	
1 Current Lin (A) * 30 Scroll down Setup Information Full URL: https://ocpp0.edde.world/0000-4 00	0001-
1 Current Lin (A) * 30 Scroll down Setup Information Full URL: https://ocpp0.edde.world/0000-4 00 Base URL: https://ocpp0.edde.world/0000-4	0001- (C)
1 Current L: (A) * 3° Scroll down Setup Information Full URL: https://ocpp0.edde.world/0000-00 Base URL: https://ocpp0.edde.wu OCPP ID: 0000-0001-00	0001- C
1 Current I: (A) * 35 Scroll down Setup Information Full URL: https://ocpp0.edde.world/0000-000 Base URL: https://ocpp0.edde.world/0000-000	0001- (C) orld (C) (C)
1 Current L: (A) * 3° Scroll down Setup Information Full URL: https://ocpp0.edde.world/0000-4 00 Base URL: https://ocpp0.edde.wu ocPP ID: 0000-0001-00	0001- (C) orld (C)
1 Current I: (A) * 3° Scroll down Setup Information Full URL: https://ocpp0.edde.world/0000-0 00 Base URL: https://ocpp0.edde.w OCPP ID: 0000-0001-00	0001- C) orld C) C)

1

EV Device

You will need one of these URLs to be entered into the EV Charger Setup. Press on the square on the right hand side to copy the value.

See your EV charger installation guide on how to enable OCPP.